


**TYPE 1**  
GRADES LESS THAN 2.00%



**TYPE 2**  
GRADES OVER 2.00%

**NOTES:**

1. Alley width can be reduced in case of existing substandard right-of-way.
2. Cross fall may be adjusted to meet existing improvements (1% min.)
3. Redwood Headers required at edge of A.C. wherever edge is not protected by other structural materials, such as existing pavement, concrete, etc.
- ⚠ 4. Concrete for valley gutter shall be Class 520-C-2500.
5. Structural section shall be as shown on plan (T.I.=5.)
6. Weakened plane joints shall be constructed in valley gutter at 10' intervals.

APPROVED *[Signature]* DATE 7-6-73  
PUBLIC WORKS DIRECTOR - R.C.E. 8134

**CITY OF RIVERSIDE**  
PUBLIC WORKS DEPT. - ENGINEERING DIV.

①	revised note 4, concrete class	W.D.	7-13-78
MARK	REVISIONS	APPR.	DATE

**ALLEY SECTIONS**

STANDARD DRAWING NO.

**110**